Energy Contract Management in the Maldives: Avoiding Claims

Read online with charts and updates:
https://risalatconsultants.com/energy-contract-management-in-the-maldives-avoiding-claims/

In short. Energy projects in the Maldives can avoid preventable claims by confirming island access before mobilisation, defining the interfaces between solar, storage and grid contracts, and acting on notices and payments within the contract timetable. Successful handover also requires evidence that the utility can operate and maintain the completed system.

Understand the delivery model before allocating risk

Distinguish generation, storage and grid works

World Bank reporting on Accelerating Sustainable Private Investment in Renewable Energy (ASPIRE) describes the use of risk mitigation to support private solar investment. The follow-on Accelerating Renewable Energy Integration and Sustainable Energy project (ARISE, P172788) combines support for solar investment with batteries and grid upgrades. The utility and project unit may therefore manage several linked obligations at one site. Check the current project documents and the signed contracts for the scope, funding and responsibilities that apply.

A private generation arrangement may have a power purchase agreement, and may use other instruments to address specific financing or payment risks. A battery supply and installation contract can have a different payment structure and testing regime. Grid reinforcement may be a utility or contractor obligation. The project needs a common schedule so that a delay in one scope is visible to the teams managing the other agreements. Each agreement still governs the rights and duties of its parties.

An official Maldives Gazette notice for the owner's engineer sets out technical advisory work on utility-scale storage, energy management systems and grid upgrading. That scope illustrates the value of a technical adviser who can examine the combined system. In practice, the agency also needs to identify which contract authorises the adviser to witness a test or recommend a decision, and which officer can actually issue an instruction or approve a payment.

Identify interfaces that can cause disputes

An interface register can state who provides civil foundations, communications, protection settings, an energised connection and the data needed to test controls. For each item, name the provider, receiver, acceptance evidence and date. Review the consequences if one party is late. Check that tender documents reflect which information is available and which assumptions bidders should price. After award, update the register using the agreed contractual communication routes.

For example, a hypothetical battery contractor can complete installation but cannot demonstrate grid response because an upstream protection upgrade is late. The project director should know who controls the upgrade, whether factory or isolated tests can proceed, and whether the proposed sequence complies with warranty and safety requirements. The contract manager should separately record notices and assess the effect on completion using the applicable terms.

Establish readiness for each island and work front

Verify access, rights and technical conditions

Before an invitation or notice to proceed, identify who controls the land, rooftops, access routes and cable wayleaves. Obtain the evidence required for the relevant stage and specify how any outstanding access will be provided. A building may be available to visit but unsuitable for equipment until the structural review is complete. A route may appear on drawings but require coordination with existing services. Have engineers and local counterparts compare drawings with actual conditions and record changes before bids are priced where feasible.

Link environmental and social commitments to each site, including consultation, contractor controls and grievance handling. Confirm the person authorised to release a work front and what that person must check. For an illustrative rooftop array, the readiness file could include access permission, engineering sign-off, an equipment lifting plan and arrangements that keep the building safe during use. Flag restrictions in the works schedule so the contractor can plan around them and the project can monitor the obligations it controls.

Plan transport and storage around island conditions

Map the path from the factory to the final installation point. Confirm berth access, lifting capacity, storage conditions, handling responsibilities and onward transport. Review how weather and sailing schedules affect the sequence, and assess realistic contingencies. Some equipment may require specific storage temperatures, security or hazardous-goods handling. Clarify which party carries these obligations and what records will be required if the planned route changes.

In an illustrative case, a container reaches the transfer port but the destination island cannot receive it for another week. A storage decision has immediate cost, safety and warranty implications. Check the notice provisions and record where the equipment is, what conditions apply and which alternatives are practical. Use the same facts to update the programme and to assess any request for time or money. A shared event record reduces the chance that parties later reconstruct incompatible timelines.

Administer changes, notices and payments

Use the contract's decision process when facts change

A site instruction should identify the issue, scope and authority under which it is issued. Where the contract requires a variation procedure, obtain the necessary approval and examine the effect on time, cost, technical performance and safeguards. A contractor's proposal can provide evidence, while the authorised engineer or employer must still make the required determination. Maintain a register of requests, notices, deadlines and decisions, with links to the relevant drawings and correspondence.

Suppose a survey identifies an underground service where a proposed cable trench should run. The engineer can first make the location safe, then confirm the obstruction, develop options and check access and permits for an alternative route. The contract manager can assess whether the revised route changes measured quantities, dependencies or the completion date. Preserve the programme before and after the event and document what each party did to mitigate the effect. This lets the parties examine entitlement and impact against the signed terms.

Certify payment using evidence prepared in advance

Establish who measures progress, who certifies work and who approves payment. Agree the billing checklist and timing, including test records, inspection sign-offs, quantities or milestone evidence. Confirm whether partial certification is available under the contract when only part of a claim is disputed. Keep the schedule of payments and cash forecast consistent with the work expected to be accepted. Where a financier's review or disbursement arrangements apply, plan the required time alongside domestic approvals.

Late reviews can complicate delivery across several islands if a supplier depends on timely payments to fund the next shipment. Monitor the age of payment applications and escalate missing client decisions promptly. A manager should be able to explain the supported amount, the reason for any deduction and the route for resolving disagreement. Record whether the underlying problem is incomplete evidence, a technical dispute, an approval delay or unavailable funding. Each needs a different corrective action.

Verify commissioning and operating capability

Define the tests before equipment arrives

Specify factory checks, site acceptance and integrated performance tests in the contract documents. For solar and battery assets, examine which tests require the grid to be energised, who supplies data and dispatch instructions, and which safety controls must be demonstrated. Clarify what happens if a test is interrupted or the required operating conditions are unavailable. Use defined thresholds and methods, and make sure there is a competent person available to witness and sign off the result.

A factory test may establish that a battery component operates within its specification. The site team still needs evidence that the installed system works with the utility's controls and protection under relevant operating conditions. If a contractual test is postponed, agree how the equipment will be maintained in the meantime and how the delay affects acceptance and warranty under the applicable terms. An installation photograph has little evidentiary value for integrated performance.

Budget for operation and maintenance

Before handover, confirm staffing, tools, spare parts, manuals, software access and support arrangements. Make the receiving utility a participant in training and testing. Ask operators to demonstrate the routines they will use, such as reading alarms and safely isolating equipment. Agree who holds the updated drawings and how changes in configuration will be recorded. Check warranty response times and how replacement items will reach outlying sites.

The implementing agency and utility can model maintenance and replacement costs alongside tariff and subsidy assumptions during design. Examine who will fund recurring expenditure and how resources will be released. If the system needs remote specialist support, establish what local staff can handle and what response time the contract provides. A maintenance budget that omits travel and spares may be inadequate even when the installation itself met the original price.

What ministries and donor-funded projects can do

Make contract management part of preparation

A ministry or project unit should review access, scope, safeguards, market capacity, cash flow and operating responsibilities before it commits to mobilisation dates. Keep a one-page summary for each site that names who can release the work front, what approvals remain, which contractor relies on another party and what evidence supports the dates. For complex procurement, test shipping and availability assumptions through documented market engagement and explain material conditions consistently to bidders.

A procurement maturity assessment can help identify weaknesses in requirements and evaluation. A project health check can identify overdue decisions between the utility, procurement team and project unit. Fund the engineering and contract administration needed to act on the findings and put those roles in place before multiple sites open.

Before authorising mobilisation, verify the work front, access rights, shipping slot, storage conditions, counterpart works, approval route and first payment milestone. Ask the utility to identify which commissioning dates depend on an action it controls.

Give the steering group evidence it can act on

Report whether each site is available, whether the next delivery can be received and whether tests can proceed. Track unanswered notices, pending changes, outstanding payment certificates and conditions for handover. Discuss exceptions with the people who can authorise a decision. If a delay affects more than one contract, update the integrated schedule and document what each party has been told. A financier can review sampled records to check that changes, acceptance and payments follow the applicable requirements.

After commissioning, compare the first operating period with the project's assumptions about availability, maintenance and support. Record lessons on site preparation, transport and how the interfaces worked. Use them to revise the next package and its acceptance tests. The project then leaves the utility with both a functioning asset and a record it can use when similar installations are planned.

Frequently Asked Questions

What commonly triggers claims on multi-island energy projects?

Unreleased sites, changes to scope or sequence, late approvals, logistics disruption and unpaid certified amounts can all generate disputes depending on the terms.

How should an agency handle a late interface between contracts?

Record the dependency and actual event, issue the applicable communications and assess mitigation, time and cost under each contract.

Does factory testing establish that a battery system is ready for service?

Site and integrated tests may also be required to show that the installed system works safely with the local grid and its controls.

What should a utility receive at handover?

Receive the agreed records, tested equipment, operating instructions, access rights, training, spares and warranty arrangements.

How can a project control variations?

Use the contractual notice and approval process, document the evidence and decide the effect on scope, cost and time.

Related Risalat programmes

- Contract Management for Donor-Funded Works Training in Dubai, Dubai (25 Jan 2027)
- Procurement, Contract Management & Effective Negotiation Training, Sofia (1 Feb 2027)
- Training on Green Public Procurement (GPP), Berlin (1 Feb 2027)
- Inclusive Public Procurement: Engaging CSOs, SMEs, Women-Owned, and Local Businesses, Seville (1 Feb 2027)

Talk to us about your institution or project: https://risalatconsultants.com/reach-risalat/